



- Easy to install
- Easy to operate
- Reliable

# For Ocean's Sake

### **Technical Specification**

**Biological Sewage Treatment Plant** 

"Ocean Clean® UltraC-9"

#### **General design features of UltraC STPs:**

- Space-saving design for corner installation
- Complete unit engineered and MADE IN GERMANY
- For black and grey water or black water only
- For gravity and vacuum systems
- Vacuum pump system available on request
- Customized solutions available on request
- Membrane system for best effluent values
- Compact, reliable and robust design
- Lifetime warranty on tank

#### **Specifications for UltraC-9:**

Designed hydraulic load: 9.3m<sup>3</sup>/d

Designed biological load: 6.5kg BOD<sub>5</sub>/d

Dimensions (LxWxH): 1965x1627x1645mm

Dry weight / wet weight: Approx. 1062 / 2495kg

Power supply: 380-690V / 50/60Hz

Power consumption: Approx. 4kW

Tank and piping material: Stainless steel: SAE grade 304

EN-standard steel no.: 1.4301

UltraC-2







Ocean Clean®- A German manufacturer of Oily Water Separators and Biological Sewage Treatment Plants.



- Easy to install
- Easy to operate
  - Reliable

#### **Contents:**

- 1. Foreword
- 2. Rules and Regulations
- 3. STP Extensions
- 4. General Description
- 5. UltraC-9 detailed description
- 6. UltraC-9 design & calculation
- 7. UltraC versions

Attachments: Operation scheme, P&ID, Drawings, Certificates

#### 1. Foreword:

The UltraC sewage treatment system (STP) is a membrane based biological treatment plant that is designated for the installation and operation on ships. The following pages show the technical specifications for the UltraC-9 and its attaching parts.

#### 2. Rules and Regulations:

Sewage treatment plants have to comply with IMO guidelines for effluent standards and undergo performance tests to ensure they are suitable to be operated on board of ships.

The UltraC STP is type approved and certified according to MARPOL 73/78 and IMO resolution MEPC.115(51) as modified by resolution MEPC.227(64) by the German Traffic Trade Association ("BG Verkehr") - Ship Safety Division.

The UltraC can be operated on board of all ships that carry more than 15 persons or are larger than 400 GRT. **The Certificates are accepted by USCG for non US-flagged vessels.** 

Effluent values of UltraC in comparison with IMO regulations						
	UltraC	MEPC.227(64)				
Total Suspended Solids	< 1 mg/l	35 mg/l				
BOD <sub>5</sub>	< 2.8 mg/l	25 mg/l				
COD	< 38 mg/l	125 mg/l				
Coliforms	< 1 per 100 ml	100 per 100 ml				
рН	7.45 - 8.08	6-8.5				
Chlorine	0.0 (not used)	0.5 mg/l				

#### 3. STP Extensions:

Galley water has to be treated by a grease trap or separator before led into the STP. Sludge tank for discharge of excess sludge has to be provided. An effluent storage tank is recommended for using the STP in areas where no liquids may be discharged overboard.





- Easy to install
- Easy to operate
- Reliable

#### "Ocean Clean® UltraC"

Biological Sewage Treatment Plant Membrane Based Bio Reactor (MBBR)



### 4. General Description:

All accessory units are mounted on the STP (except vacuum unit), with all internal piping and wiring, completely checked and tested, ready to plug on. The black water and grey water flows by gravity (vacuum on request) into the STP. Galley water must be led through a grease trap or separator. Incurred excess sludge inside the STP must be discharged acc. instructions into a sludge tank.

The "UltraC-9" is a three chamber system:

Coarse material is removed in the first stage (coarse material tank). Pre-cleaned sewage enters the second stage (activation tank) where it is mixed with activated sludge, i.e. microorganisms that metabolize the organic pollution into CO<sub>2</sub> and water. Filter membranes in the last stage (filter tank) separate the cleaned water from the activated sludge, viruses and bacteria. A filtrate pump discharges the cleaned water into a filtrate tank or directly overboard.

#### Activated sludge for starting up has to be provided by yard from municipal sewage plant!

Ambient air is fed into the STP to support the biological process. The biology has to be checked by taking samples on a regular basis. Only biodegradable waste may be led into the STP. Excessive use of detergents or hazardous substances can destroy the biology and cause malfunctions of the STP.

In accordance with the SOLAS regulation II-I/3-5, new installation of asbestos in context with IMO MSC.1/Circ.1374 and 1379, all materials, products and components including packaging by our company are completely free of asbestos.



- Easy to install
- Easy to operate
- Reliable

## 5. "UltraC-9" - detailed description:

#### **Electrical system and attached parts:**

The electrical control cabinet, including transformer, sensing relays, all necessary switches, control relays and control lamps (LED), is made of mild steel, protected according to IP66, coated with finish RAL 7035 and equipped with cable glands with stuffing bushes acc. to DIN 89280 and door stoppers.

Start-stop level for transfer pump and high level alarm are measured by level switches. One potential-free contact for a common alarm to ECR is provided.

#### Fine screen

Coarse material that enters the STP is held back by **self cleaning fine screen**. The cleaning is carried out with brushes and an electrical gear motor.

Technical details fine screen motor:							
Protection class	IP 55, ISO class F						
Power [kW]	0.12						
Speed [rpm]	6						

#### Circulation and sludge discharge pump

The biologically active liquid ("activated sludge") and raw sewage are circulated inside the STP to create an even mixture to enable the microorganisms to reduce the pollution. The activation tank is constantly re-circulated to the membrane tank to supply the membrane filter with activated sludge. The **circulation pump** is also used to discharge excess sludge and coarse material and to empty the STP.

#### Filtrate pump

The **filtrate pump** is used to discharge cleaned water via the membrane filter.

Technical details circulation pumps / filtrate pumps:						
	Circulation pump Filtrate pump					
Туре	Eccentric screw pump with mechanical seal					
Flange sizes suction / discharge side	DN25, PN16					
Protection class	IP 55, ISO class F					
Capacity [m³/h] at [bar]	1.0 at 6 0.5 at 6					
Power [kW at Hz] 0.55 at 50 0.37 at 50						

The filtrate pumps must not be used to empty the STP!

Furthermore, the membrane filter may not dry out once it has been in contact with water. The sensitive material would become brittle and cannot be used again.





- Easy to install
- Easy to operate
- Reliable

#### Air blower

The air feed of the STP is supplied by **side channel blower**. They force ambient air into the tanks via submerged aeration elements (breather tubes) that both support the biology and clean the membrane filter.

Technical details side channel blowers:						
Air flow [m³/h]	80					
Pressure [mbar]	250					
Power [kW at Hz]	1.6 at 50 / 2.05 at 60					

#### Sensors

Suction pressure (one **vacuum meter**) is measured between filtrate pump and membrane filter to prevent the membrane from destruction and to determine the time for a chemical membrane cleaning.

Low level, high level and alarm level are sensed by **float switches** inside the activation tank.

#### Tank:

- The UltraC is a three tank system:
  - In the first tank coarse material is separated from the sewage.
  - The second tank is to activate and accelerate the biological process.
  - In the third tank the activated sludge is separated from the cleaned water by a filter membrane. Tank two and tank three are separated. This is to ensure the membrane is always submerged. Furthermore, this allows cleaning of the membrane without discharging all activated sludge.
- All tanks are accessible via manholes either on top or on the sidewalls of the tank. Flanges for inlet and ventilation pipes are on the top of the STP.
  - The control panel as well as all pumps, blower and instruments are located on the front or one side of the unit for easy access and a minimum footprint and maintenance space.
- Tank and piping made of stainless steel.

#### **Connections:**

- For electrical connections please refer to the electrical diagram.
- The UltraC is factory tested and ready to plug in. It needs to be fixed to the floor by welding or bolting. The necessary pipe connections need to be established:

Pipe connection:	Inlet	Ventilation	Overflow	Outlet	Flushing	Discharge
Size [DN]	DN100	DN100	DN25	DN25	DN25	DN25
Size [PN]	PN16	PN16	PN16	PN16	PN16	PN16





- Easy to install
- Easy to operate
- Reliable

#### 6. UltraC-9 - design & calculation

The UltraC-9 is designed, calculated and type approved to treat a maximum hydraulic load of 9.3m³/d and a biological load of 6.5kg BOD₅/d according to the guidelines and specifications of the German BG Verkehr as responsible authority:

		H	Resulting No. of persons				
Min. requirements acc. BG Verkehr	Grey Water	Black Water Vacuum		Total Vacu- um System	Total Gravi- ty System	Vacuum System	Gravity System
Passenger vessel	160	25	70	185	230	50	40
Seagoing ship except	110	25	70	135	180	68	51

The Ocean Clean calculation is based on experienced data and customer feedback:

			<u> </u>					
		H	Resulting No. of persons					
Requirements accor	Requirements according to OC experience							
Barge	35	15	35	50	70	186	132	
Commercial vessel	95	25	55	120	150	77	62	
Naval vessel	135	20	65	155	200	60	46	
Stationary Platform	175	25	70	200	245	46	38	
Yacht (charter)	190	25	75	215	265	43	35	
Working ship	190	25	75	215	265	43	35	
River Cruiser	210	25	75	235	285	32	32	
Cruiser	240	25	75	265	315	35	29	
Yacht (owner)	350	25	75	375	425	24	22	

Please see the attached project-specific calculation for further details and a load forecast.

To ensure a solid biological process the feeding of the UltraC-9 should not fall below the following values:

	Long-term	Short-term	Design maximum
Hydraulic load	4.65m³/d	2.75m³/d	9.3m³/d
Biological load	4.55kg/d	1.95kg/d	6.5kg/d

As a biological system the UltraC is sensitive to the sewage quality. Intensive use of strong detergents or the inlet of chemicals (e.g. chlorine) will destroy the microorganisms of the activated sludge. Insufficient feeding may reduce the concentration of microorganisms severely and cause difficulties when feeding the STP with the standard load.

Flushing the plant and emptying it completely requires to fill in new activated sludge to restart the biological process.

The quality of the activated sludge needs to be checked on a regular basis. Otherwise the membrane filter may clog or get damaged which will make an exchange-service or a chemical cleaning necessary.





- Easy to install
- Easy to operate
- Reliable

#### 7. UltraC - version overview


The UltraC STP is available in different versions and sizes. Following table lists the general standard types.


Range of <b>UltraC</b> types - other sizes available on request							
Туре	Max. hydraulic load [m³/d]	Max. biological load [kg BOD₅/d]	Collecting tank [m³]	Length [mm]	Width [mm]	Height [mm]	Net weight [kg]
UltraC-2	2.7	1.9	-	1927	1553	1645	826
UltraC-5	5.0	3.5	-	1927	1627	1645	1062
UltraC-9	9.3	6.5	6.0	1927	1627	1645	1062
UltraC-10	10.0	7.0	-	3911	1999	2112	1967
UltraC-15	15.0	10.6	-	5483	2130	2091	2815
UltraC-27	27.8	19.6	18.0	5483	2130	2091	2815


Please note that a sufficient maintenance space is always needed to guarantee a good access to all components. The maintenance space requirement of the UltraC is very small. Please note the attached drawings for details.


Images and diagrams for illustration only. Subject to technical changes and misprints.


















Number	Description	Size				
1	Sewage Inlet	DN100/PN16				
2	Deaeration	DN100/PN16				
3	Flushing Connection	DN25/PN16				
4	Sludge Discharge	DN25/PN16				
5	Filtrate Discharge	DN25/PN16				
6	Emergency Overflow	DN25/PN16				
Do not roduce dispotent of output /discharge pipeel						

Do not reduce diameter of output/discharge pipes!

Deaeration pipe has to be steadily rising!

Rev	Revision: 0		Obe	erfläche:		Maßstab:1:50   Gewicht: dry1062kg/wet2498   Werkstoff:			
					Datum	Name	†		
				Erst. 04.11.2015 M.Hille Gepr.		UltraC-9			
				Freig.					
					Ocean Clean GmbH Zum Kühlhaus 5 18069 Rostock				
				1					۱۵
				Germany Phone: +49 (0) 381-811 2930		000	0 00 000	Seite 1/2	
				Fax:	+49 (0) 381	-811 2939	005-0	9-BG-000-00	
Index	Änderung	Datum	Name	info@	oceanclean.c	de			A3

Preliminary drawing. Subject to technical changes and misprints.





# TYPENPRÜFUNGSZEUGNIS für Abwasser-Aufbereitungsanlagen

Certificate of Type Approval for Sewage Treatment Plants

#### Ausgestellt im Namen der Regierung der BUNDESREPUBLIK DEUTSCHLAND durch die BERUFSGENOSSENSCHAFT FÜR TRANSPORT UND VERKEHRSWIRTSCHAFT

Issued under the authority of the FEDERAL REPUBLIC OF GERMANY by Berufsgenossenschaft für Transport und Verkehrswirtschaft

Hiermit wird bescheinigt, dass die Abwasser-Aufbereitungsanlage This is to certify that the sewage treatment plant

Typ:	UltraC-9							
type:								
Ausgelegter Flüssigkeitsdurchsatz: $9,30 \text{ m}^3/\text{Tag}$ having a designed hydraulic loading of: $m^3/d$								
Durchsatz an organ								
Auslegung gemäß and of the design sho	Zeichnungen Nrn.: ocs-c25-BG000 own on drawings Nos.:							
Hergestellt durch: manufactured by:	Ocean Clean GmbH, Zum Kühlhaus 5, 18069 Rostock							
Betrieb gemäß Re Meeresverschmutzu Entschließung MEP has been examined an the operational requi	rzogen und in Übereinstimmung mit der IMO-Entschließung MEPC.227(64), um die Anforderungen an den egel 9.1.1 und 9.2.1 MARPOL Anlage IV des Internationalen Übereinkommens zur Verhütung der ung durch Schiffe, 1973, geändert durch die Protokolle von 1978 und 1997 (in der geänderten Fassung der PC.115(51) und MEPC.200(62), zu erfüllen, zufriedenstellend erprobt wurde.  Ind satisfactorily tested in accordance with the International Maritime Organization resolution MEPC.227(64) to meet irements referred to in Regulation 9.1.1 and 9.2.1 of MARPOL Annex IV of the International Convention for the from Ships, 1973, as modified by the 1978 and 1997 Protocols (as amended by resolutions MEPC.115(51) and							
	er Abwasser-Aufbereitungsanlage wurden durchgeführt ge treatment plant were carried out							
an Land bei*: Kashore at:	Klärwerk Wismar - Wendorf							
an Bord von*:	-							
und abgeschlossen and completed on:	am: 02.07.2011							

Zulassungs-Nr.: 340.464 *Certificate-No.:* 

<sup>\*</sup> nicht zutreffendes streichen Delete as appropriate

Bei der Erprobung wurde ein Abfluss festgestellt, der nach der analytischen Untersuchung folgende Ablaufwerte hat: *The sewage treatment plant was tested and produced an effluent which, on analysis, produces:* 

- (.1) ein geometrisches Mittel von nicht mehr als 100 fäkalkoliforme (thermo-toleranten) Bakterien/100 ml
- (.1) a geometric mean of no more than 100 thermo tolerant coliforms/100 ml;
- (.2) ein geometrisches Mittel der gesamten Schwimm- und Schwebstoffe von 35 Qi/Qe mg/l für an Land getestete Anlagen oder der Maximalwert der gesamten Schwimm- und Schwebstoffe übersteigt nicht (35 plus x) Qi/Qe mg/l für das umgebende Wasser, das für Spülzwecke verwendet wird, bei Tests an Bord
- (.2) a geometric mean of total suspended solids of 35 Qi/Qe mg/l if tested ashore or the maximum total suspended solids not exceeding (35 plus x) Qi/Qe mg/l for the ambient water used for flushing purposes if tested on board
- (.3) ein geometrisches Mittel des Biochemischen Sauerstoffbedarfs nach fünf Tagen ohne Nitrifikation (BSB<sub>5</sub> ohne Nitrifikation) mit nicht mehr als 25 Qi/Qe mg/l
- (.3) a geometric mean of 5-day biochemical oxygen demand without nitrification (BOD<sub>5</sub> without nitrification) of no more than 25 Qi/Qe mg/l
- (.4) ein geometrisches Mittel des Chemischen Sauerstoffbedarfs (COD) mit nicht mehr als 125 Qi/Qe mg/l
- (.4) a geometric mean of chemical oxygen demand (COD) of no more than 125 Qi/Qe mg/l
- (.5) der pH-Wert liegt zwischen 6 und 8,5
- (.5) pH between 6 and 8,5
- (.6) ein geometrisches Mittel des gesamten Stickstoff von nicht mehr als 20 Qi/Qe mg/l oder mindestens 70 % Reduktion, u.
- (.6) a geometric mean of total nitrogen of no more than 20 Qi/Qe mg/l or at least 70 per cent reduction; and
- (.7) ein geometrisches Mittel des gesamten Phosphor von nicht mehr als 20 Qi/Qe mg/l oder mindestens 80 % Reduktion
- (.7) a geometric mean of total phosphorus of no more than 1,0 Qi/Qe mg/l or at least 80 per cent reduction\*\*

Die Verwaltung bescheinigt, dass die Anlage bei Neigungen bis zu 22,5° in jede Richtung von der normalen Aufstellung arbeiten kann.

The Administration confirms that the sewage treatment plant can operate at angles of inclination of 22.5° in any plane from the normal operating position.

Einzelheiten der Erprobungen und der einzelnen Ergebnisse werden im Anhang aufgezeigt.

Details of the tests and the results obtained are shown on the Appendix to this certificate.

Ein Schild oder ein haltbarer Aufkleber muss an jeder Abwasser-Aufbereitungsanlage angebracht sein mit Angaben über den Hersteller, Typ und die Seriennummern, den Flüssigkeitsdurchsatz und das Herstellungsdatum.

A plate or durable label containing data of the manufacturer's name, type and serial numbers, hydraulic loading and date of manufacture should be fitted on each sewage treatment plant.

Eine Kopie dieses Zeugnisses muss auf jedem Schiff mitgeführt werden, das mit der oben beschriebenen Abwasser-Aufbereitungsanlage ausgerüstet ist.

A copy of this certificate shall be carried on board any ship equipped with the above described sewage treatment plant.

Dieses Typenprüfungszeugnis gilt bis:

30.09.2020

This certificate of type test is valid until

Dieses Typenprüfungszeugnis bleibt über das vorstehende Datum hinaus in Kraft, sofern kein Widerruf erfolgt.

Ein Widerruf für auf einem Schiff eingebaute Einrichtungen kann z.B. erfolgen, wenn diese nicht gefahren und/oder nicht gewartet und/oder nicht funktionsbereit sind und/oder nicht innerhalb einer angemessenen Frist an zukünftige Bestimmungen angepasst werden können.

This certificate of type test is in force beyond the above mentioned date unless it is revoked.

A revocation of the equipment installed aboard the ship can follow, but is not limited to, if the equipment is not maintained and/or is not in good working order and/or the equipment can not be modified within an appropriate time frame, due to future regulatory standards.

<sup>\*\*</sup> ist zu streichen für Schiffe, die keine Fahrgastschiffe sind die beabsichtigen Abwasser in Sondergebieten einzuleiten Delete for ships other than passenger ships intending to discharge sewage effluent in Special Areas

Das Typenprüfungszeugnis für Type UltraC-9 wird aufgrund der Erprobung von Type OCS-compact 15 gemäß IMO-Entschließung MEPC.227(64) Anhang Pkt. 5.8 ausgestellt.

The certificate of type test of type UltraC-9 will be issued based on the test of type OCS-compact 15 according to IMO-Resolution MEPC.227(64) annex 5.8.

Ausgestellt in Hamburg

Issued at Hamburg

am 01.10.2015

BERUFSGENOSSENSCHAFT FÜR TRANSPORT UND VERKEHRSWIRTSCHAFT - DIENSTSTELLE SCHIFFSSICHERHEIT -

Unterschrift Signature

Die Abwasser-Aufbereitungsanlage Serien-Nr. The sewage treatment plant serial No.		 entspricht dem geprüften Typ. complies with the tested type.	
Ort Place	Datum date	 Firmen- stempel Company stamp	Unterschrift Signature



## TYPENPRÜFUNGSZEUGNIS für Abwasser-Aufbereitungsanlagen

Certificate of Type Test for Sewage Treatment Plants

ANHANG zu Type: UltraC-9
Appendix to type: UltraC-9

Prüfergebnisse und Einzelheiten der Erprobungen, geprüft mit Hilfe von Proben der Abwasser-Aufbereitungsanlage in Übereinstimmung mit der Entschließung MEPC.227(64)

Test results and details of tests conducted on samples from the sewage treatment plant in accordance with resolution MEPC.227(64)

Abwasser-Aufbereitungsanlage, Typ:	OCS-compact 15					
Sewage treatment plant, Type:						
Hergestellt durch: Ocean Clean GmbH  Manufactured by:	I, Zum Kühlhaus 5, 18069 Rostock					
The state of the s	BG Verkehr, Dienststelle Schiffssicherheit					
Organization conducting the test:	, , , , , , , , , , , , , , , , , , , ,					
Ausgelegter Flüssigkeitsdurchsatz	2,7	Kubikmeter pro Tag				
Designed hydraulic loading		cubic metres per day				
Ausgelegter Durchsatz an organischen Stoff	<u>1,9</u>	Kilogramm pro Tag BSB				
Designed organic loading		kilograms per day BOD				
Anzahl der untersuchten Ausflussproben	40					
Number of effluent samples tested						
Anzahl der untersuchten Einlaufproben	40					
Number of influent samples tested						
Abwasserqualität (Einlauf), TSS Total suspended solids influent quality		Milligramm pro Liter Schwebestoffe milligrams per litre Total Suspended Solids				
Gesamtstickstoff am Einlauf	n.a.	Milligramm pro Liter als Stickstoff*				
Total nitrogen influent quality		milligrams per litre as nitrogen*				
Gesamtphosphat am Einlauf	n.a.	Milligramm pro Liter als Phosphat*				
Total phosphorus influent quality		milligrams per litre as phosphorus*				
BSB <sub>5</sub> ohne Nitrifikation am Einlauf	704	Milligramm pro Liter				
BOD <sub>5</sub> without nitrification influent quality		milligrams per litre				
Maximaler Flüssigkeitsdurchsatz	2,7	Kubikmeter pro Tag				
Maximum hydraulic loading		cubic metres per day				
Mindest-Flüssigkeitsdurchsatz		Kubikmeter pro Tag				
Minimum hydraulic loading		cubic metres per day				
Durchschnittlicher Flüssigkeitsdurchsatz	2,7	Kubikmeter pro Tag cubic metres per day				
Average hydraulic loading	2.7	3.000-000000000000000000000000000000000				
Abwasserauslauf (Qe)  Fffluent flow (Qe)	2,7	Kubikmeter pro Tag				

<sup>\*</sup> nicht zutreffendes streichen Delete as appropriate

_1	
1 Milligramm pro Liter milligrams per litre	
Bakterien pro 100 Milliliter coliforms per 100 millilitres	
2,8 Milligramm pro Liter milligrams per litre	
37,5 Milligramm pro Liter milligrams per litre	
n.a. Milligramm pro Liter* oder Prozent*  milligrams per litre* or per cent*	K
n.a. Milligramm pro Liter* oder Prozent*  milligrams per litre* or per cent*	ķ
8,08	
7,45	
Milligramm pro Liter milligrams per litre	
Milligramm pro Liter milligrams per litre	
Milligramm pro Liter milligrams per litre	
ja/yes ⊠ nein/no □ *	
ja/yes ☐ nein/no ☑ *	
ja/yes ☐ nein/no ☑ *	
ja/yes ⊠ - Anteil % nein/no □ * - proportion	
l	1 Milligrams per litre 1 Bakterien pro 100 Milliliter coliforms per 100 millilitres 2,8 Milligramm pro Liter milligrams per litre 37,5 Milligramm pro Liter milligrams per litre  n.a. Milligramm pro Liter* oder Prozent* milligrams per litre* or per cent*  n.a. Milligramm pro Liter* oder Prozent* milligrams per litre* or per cent*  8,08  7,45  Milligramm pro Liter milligrams per litre  Milligrams per litre

<sup>\*</sup> nicht zutreffendes streichen Delete as appropriate

MEPC.227(64) festgelegt sind:  Was the sewage treatment plant tested against the environmental conditions specified in section 5.9 of resolution MEPC.227(64):							
	Temperatur Temperature		ja/yes 🛭	nein/no □ *			
	Luftfeuchtigkeit Humidity		ja/yes 🛭	nein/no □ *			
	Krängung Inclination		ja/yes 🔀	nein/no □ *			
	Vibration Vibration		ja/yes 🔀	nein/no □ *			
	Funktionssicherheit der elekt Reliability of Electrical and Elec	r. und elektronischen Bauteile etronic Equipment	ja/yes 🗵	nein/no □*			
	gen und Betriebsbedingungen ad the conditions of operation are	imposed:					
	SalzgehaltSalinity		<u></u>				
	Temperatur		5 - 45 °C				
	Luftfeuchtigkeit		<del></del>				
	Krängung		<del></del>				
	Vibration						
	nderer geprüfter Parameter: er parameters tested	keine none					
	inschränkungen: itions imposed:						
Die Abwasse	r-Aufbereitungsanlage UltraC-	9 muss mit einem Vorhaltetan	k von min. 6,0	m³ ausgerüstet werden.			
The sewage tr	eatment plant UltraC-9 should be	equipped with a pre collecting to	ink of min. 6,0 m <sup>3</sup>				
Ausgestellt in	n: Han	ıburg	am:	01.10.2015			
Issued at:			on:				
	Transport						

Wurde die Abwasser-Aufbereitungsanlage geprüft nach den Umweltbedingungen die in Abschnitt 5.9 der Entschließung



Berufsgenossenschaft für Transport und Verkehrswirtschaft - Dienststelle Schiffssicherheit -

<sup>\*</sup> nicht zutreffendes streichen Delete as appropriate



European notified body Identification number 0736



### EC-Type Examination (Module B) Certificate

Certificate-No.

340,464

Name and address of the

manufacturer:

Ocean Clean GmbH, Zum Kühlhaus 5, 18069 Rostock, Germany

Date of issue:

01.10.2015

Annex A.1 Item No & Item designation

A.1/2.6 - Sewage treatment plants

Product designation:

Sewage treatment plant

Product Type:

UltraC-9

Intended purpose:

Sewage treatment plants for ships acc. MARPOL 73/78, Annex IV and

Helsinki-Convention

Testing based on (Specific standard): IMO Resolution MEPC.227(64) for sewage treatment plants in acc. with

MARPOL 73/78, Annex IV, Reg. 9

Remarks

The type tested was found to be in compliance with the Marine-pollution prevention requirements of Marine Equipment Directive (MED) 96/98/EC as amended by Directive 2014/93/EC subject to any conditions in schedule (part of this certificate).

This certificate may only be used in connection with module(s) **D** or **F** or

Expiry date:


30.09.2020

Installed equipment stays approved beyond the validity date until it is revoked!

Note 1: This certificate will not be valid if the manufacturer makes any changes or modifications to the approved equipment, which have not been notified to, and agreed with the notified body named on this certificate.

Note 2: Should the specified regulations or standards be amended during the validity of this certificate, the product(s) is/are to be re-approved prior to it/they being placed on board vessels to which the amended regulations or standards apply.

Note 3: The Mark of Conformity may only be affixed to the above type approved equipment and a Manufacturer's Declaration of Conformity issued when the production-control phase module (D, E, or F) of ANNEX B of the Directive is fully complied with and controlled by a written inspection agreement with a notified body.



Note 4:

"Wheelmark" Format

YY

Last two digits of year mark affixed.

XXXX Notified Body number undertaking surveillance module

Postal address: Ottenser Hauptstraße 54 22765 Hamburg

xxxx/yy

Office: Brandstwiete 1 20457 Hamburg Tel: 0 40/3 61 37-0 Fax: 0 40/3 61 37 2 04

In any case, the German original shall prevail


## Technical data/approved drawings and additional conditions and remarks:

The Prüf- und Zertifizierungsstelle of the BG Transport und Verkehrswirtschaft verifies and certifies the conformity of the above mentioned product in accordance with the Directive 96/98/EC of the Council as amended (last amendment by directive 2014/93/EC), Annex B, Module D or Module F (Product Verification), section 5, Statistical Verification.

All products will be divided into identical lots of 10 pieces each, starting with serial number OCS-YYMM-0101-XXXX. One (1) random sample will be drawn from each lot and individually examined.

## Fat Trap **Operation Scheme**








A grease trap removes fat, oil and grease (called FOG) and solids (food particles, sand and grit etc.) by a gravity separation process.


The grease trap slows down the flow of waste water long enough for the FOG and solids to separate. The solids settle to the bottom and the grease floats to the top. The middle layer is free water which is discharged to the sewer.

The longer the flow is kept inside the trap, the better job it will do of separating the waste materials.









_										
Revision:			Oberfläche:		Maßstab:1:5   Gewicht: 38.21kg   Werkstoff:					
				Datum Name		Stainless Steel				
					Erst.	02.12.2015	M.Hille	Fat Tran	50VA DN80	
					Gepr.			i at map	00 V/ ( D1 100	
					Freig.					
				Ocean Clean GmbH Zum Kühlhaus 5						
					Germ	9 Rostock				Seite
			Phone: +49 (0) 381-811 2930			FT-50VA-BG-100				
	Fa			Fax:	+49 (0) 381	-811 2939				
ndex Änderung Datum Name			info@oceanclean.de			A3				